BANGALORE DIVISION.

Notice dated 2nd September 1929.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 16th September 1929, for Restoring Huralihalli Kodagikere Regd. No. 68 of Nelamangala Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A M. and 5 P.M., on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

3. (*a*) Tender quoting percentage below estimate will not be received.

4. Each tender must be accompanied by a deposit of Rupees three hundred in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Restoring Huralihalli Kodagikere Regd. No. 68", in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of Huralihalli Kodagikere, Regd. No. 68 of Nelamangala Taluk.

No.	Items of work	Per	Quantity	Rate
	Bund.			
1	Clearing jungle and cutting grips	Grade	13	
2	Earthwork to bund with consolidation ...	C.yds.	9,967	
3	New stone work	,,	742	
4	Old stone with new jelly	,,	84	
5	Turfing	S.yds.	4,700	
6	Providing new grade stones	Each	14	
7	Do index stones	,,	14	
8	Do B. M. stones	,,	2	
9	Do Reg. No. stone	,,	1	
10	Do Gauge stone	,,	1	
	Constructing Sluice as per Type Design. Waste Weir at Right to R. L. 54·00			
1	Earthwork, hard soil	C.yd.	75	
2	Burnt brick in surki mortar.	C.ft.	1,299	
3	Burnt stone slabs roughly dressed	S.ft.	503	
4	Plastering with surki mortar	Sqr.	13·56	
5	Rough stone work new	C.yd.	195	
6	Old stone work	,,	26	
7	Filling up the lower and undulated portions of toe of apron.	L. S.	...	

H. R. VENKATASUBBA RAO,
Executive Engineer.